OPTION 1 : LONG TERM COMBINED REPLACE POLICE/FIRE STATIONS

WOODSIDE AVE

EXISTING PATH

SECURITY FENCE

STRUCTURAL PLATE ARCH CULVERT-12' SPAN 4'RISE WITH CONCRETE HEADWALL

COVERED/ENCLOSED APPARATUS PARKING/PROPERTY STORAGE

ENCLOSED PARKING

12" STORM DRAIN

CREEK

STRUCTURAL PLATE ARCH CULVERT-12' SPAN 4'RISE WITH CONCRETE HEADWALL

RETAINING WALL

DETENTION BASIN

12" STORM DRAIN

STERLING HIGHWAY

PROPOSED 6" SANITARY SEWER CONNECTION

EXISTING HYDRANT

EMERGENCY GENERATOR

77 TOTAL SPACES

DUMPSTER

PROPOSED HYDRANT

PROPOSED 8" WATER SERVICE

COVERED PARKING

BIKE RACKS

129.0 FFE

118.5 FFE

DETENTION BASIN

COVERED PARKING

EXISTING HYDRANT

PROPOSED 8" WATER SERVICE

PROPOSED 18" STORM DRAIN

HOMER AVE

SCALE IN FEET

IMAGE DATE: 05/12/2011

FILE: C:\USERS\GLARSEN\DESKTOP\L-SP-OPTION 1 ORIGINAL.DWG PLOTTED: Dec 21, 2015 - 8:36:21 AM (Larsen, Georgio)

REVISIONS

No.	Date	Revision	By

Date Stamped:

Stantec

2515 'A' Street
Anchorage, Alaska 99503
Phone: (907) 274-2245
FAX: (907) 258-4653
www.stantec.com

Project:
HOMER PUBLIC SAFETY BUILDING

City of Homer
Homer, Alaska 99603

Project Mgr.	DRS
Drawn	
Checked	
Date	12/17/2015

Sheet Contents:

OPTION 1

Sheet No.:

L1.1

Project Number: 204600234

THIS DRAWING IS HALF-SIZE AT 11"x17"