

ADDENDUM NO. #2

Project: Kachemak Drive Water and Sewer Improvements (Phase III)
Addendum Issue Date: August 29, 2016
Bid Date: September 1, 2016 @ 2:00 PM (Thursday)
Previous Addenda Issued: Addendum #1
Issued By: Carey Meyer
City Engineer
City of Homer
Homer, AK 99603
cmeyer@ci.homer.ak.us

Bidders must acknowledge receipt of this addendum prior to the date set for bid opening by one of the following methods:

- (1) By acknowledging receipt of this addendum in the bid submitted (**use addendum acknowledgement form provided in bid documents**).
- (2) By facsimile (fax) or email which will need to include a reference to the project and each of the addendum numbers.

The bid documents require acknowledgement individually of all addenda to the drawings and/or specifications. This is a mandatory requirement and any bid received without acknowledgment of receipt of addenda may cause the bid to be considered non-responsive.

ITEM 1 – Will air testing of sewer be allowed?

Yes, 2 psi for 20 minutes (with no pressure loss).

ITEM 2 – Does city require the removal of welded beads in sewer?

No.

ITEM 3 – I didn't see a spec for the locate wire connections on the sewer?

All HDPE mainline shall be installed with No. 6 bare copper locate trace wire. Trace wire will be secured to the top of the pipe with tape or other approved method at minimum ten foot intervals.

ITEM 3 – Question from Addendum #1 - Can water services from the main to the property line be HDPE ?

We changed our minds – Yes, water services from main to property line can be HDPE.

END ADDENDUM #2