



## **Proposed New Projects Table of Contents**

---

### **City of Homer Projects**

1. Port & Harbor: Wood Grid Replacement..... 2

### **Projects Submitted by Other Organizations**

2. South Peninsula Hospital: Hillside Stability Survey ..... 3

**PROPOSED NEW PROJECT - DRAFT**



## Port & Harbor Wood Grid Repaclement

**Project Description & Benefit:** The Wood Grid is a series of benches (in this case wooden beams) laid out on intertidal land that can support a boat for hull repairs during low tides. Vessels float over the grid at high tide and then set down on the grid as the tide resides. Vessel owners are able to do minor repairs and inspections to their vessels hulls while “dry” on the grid and refloat with the incoming tide.

The Wood Grid is one of two tidal grids that the Port and Harbor operates. Because of our large tidal exchange in Kachemak bay, Homer’s tidal grids are likely one of the most useful vessel grid systems in the world. They utilize the tides to our advantage to provide an inexpensive way for vessel owners to maintain their vessels’ hulls.

Homer’s Wood Grid was originally built 40 years ago and accommodates vessels up to 59 feet with a 50 ton limit. Other than the walkway replacement that occurred in 2001, the wood grid has seen very little in terms of upgrades since.

Three particular issues would likely be addressed in an upgrade. Gravel has migrated downhill and filled in between the benches, making it increasingly difficult for people to actually to get under the vessels on the grid to perform repairs. A second issue is with the Wood Grid’s retaining walls. Due to age, the upper wall is no longer retaining infill from the bank above and the lower submerged wall has degraded to the point that staff are not able to repair it. Another concern is that the benches and the buried pile that support them have deteriorated to the point that staff is unable to repair them. At a minimum the piles and benches will need to be replaced.

**Plans and Progress:** This project would consist of two phases. The first phase is preliminary engineering and design to ascertain the scope and cost of the improvement. The second phase would be construction.

**Total Project Cost:**

Phase 1: Engineering and design: \$25,000

Phase 2: Construction: to be determined in Phase 1.

**Schedule:** 2018

**Priority:** 2



The Wood Grid in Homer’s Port and Harbor was originally built 40 years ago and accommodates vessels up to 59 feet with a 50 ton limit. Other than replacing the walkway in 2001, the wood grid has seen very little in terms of upgrades since.

PROPOSED NEW PROJECT - DRAFT



## South Peninsula Hospital: Hillside Stability Survey

---

**Project Description & Benefit:** South Peninsula Hospital sits on a very steep hillside, with all parking lots and outbuildings being terraced down from the main hospital building. Both the lot the hospital sits on and the lot behind it continue with a very steep elevation incline. The buffer is only 12 feet behind the building cut into the hillside before the terrain continues with the steep incline for as far as 300 yards. The remaining hillside has thick vegetation and is not utilized or developed in any way at this time.

The facility has had numerous additions and structural work completed in the last 10 years which may have impacted and affected the stability of the hillside. The hillside runs continuous from the entrance of parking the entire length of the building and beyond. No part of the main hospital building is out of the risk zone for damages from hillside erosion and sloughing.

A site evaluation is necessary to establish the current condition of the hillside, and make any recommendations to secure it from further erosion and sloughing. Such evaluation would include a survey, soils testing, geologic hazard assessment and mitigation report, landslide evaluation, earthquake assessment, and recommendations for options to minimize risk to the facility. The recommended options would include cost estimates.

**Plans and Progress:** The estimated cost of such a study, evaluation, and report is \$100,000. This could include work by the Army Corps of Engineers, and/or a private engineering firm.

**Total Project Cost:** \$100,000

**Schedule:** 2018



A hillside stability study on the slope behind the South Peninsula Hospital will yield recommendations on ways to minimize risk to the facility.

PROPOSED NEW PROJECT - DRAFT