

Resolution 25-064, A Resolution of the City Council of Homer, Alaska Authorizing the Staff of the Homer Public Library to Apply for Grants for the Purpose of Funding the Purchase and Installation of the Library Security Grille. City Manager/Library Director.

Item Type: Backup Memorandum

Prepared For: Homer Mayor and City Council

Date: June 17, 2025

From: Library Director Dave Berry

Through: City Manager Melissa Jacobsen

Background

During the design process for the current Homer Public Library building, the architects envisioned installing a security grille between the meeting room and the main floor, allowing the meeting room to be used outside of library hours. That grille was never installed, but we have an opportunity to do so now.

The library receives many meeting-room requests from community groups, and we would likely receive more if the room were available after hours. Installing a grille enhances the value of a resource that is already in high demand and that the community worked hard to build.

Usage Questions

I communicated with a number of other library directors that have similar systems. How much the room is used after hours depends on the library's fees and policies, but in general the public appreciated having extended meeting hours and used the facilities responsibly. No one reported any problems with theft or vandalism.

Library staff here in Homer would copy the procedures used in places like Palmer and Big Lake, where groups must be present at closing time and staff lock both the grille and the outside door, leaving the group to use the room in between. Groups must ensure the outside door latches when they leave. I would like to emphasize that **the outside door of the building would never be left open overnight.**

Project Status

Last year, the City Council approved Ord. 24-24(A), allocating \$30,000 for designing and installing a grille. As of June 2025, all the engineering work is complete, and the State Fire Marshal has issued a permit approving the design. The cost estimates provided in February suggest we would need roughly another \$19,000 to complete the installation.

I recommend pursuing grant funding in the amount of \$25,000, to allow for inflation or unexpected contingencies. The project offers long-term benefits to the community as a whole, which should make it appealing to potential grantors.

RECOMMENDATION:

Adopt Resolution 25-064

ATTACHMENTS:

FAQ About the Library Security Grille Mockup Photographs of the Grille Site Engineering Design Drawings Fire Marshal's Certificate of Plan Review Product Specifications Brochure Final Cost Estimates

Library Security Grille FAQ

Q: What's the security grille for?

A: There's a lot of competition among groups that want to use the meeting room in the evening, particularly for adults meeting after work. Installing a security grille means the room would be usable after hours without needing staff to be present.

Q: Is this a new idea?

A: No. In their original design for the library building, the architects explicitly conceived of a meeting room that "can be accessible after library hours without going into the main floor." Such a feature is common in other public buildings—the Port and Harbor Office here in town has a similar setup, as do many public libraries in other cities.

Q: Does this mean the library will be unlocked all night?

A: No. Here's the process for using the room after hours:

- A group must fill out a room-reservation form, just as they do now. Anyone reserving
 the room must be at least 18 and all reservations are subject to approval by library
 staff.
- 2. The group must have a representative present in the library at closing time.
- 3. Staff will lock the outside door of the building and the security grille, leaving the group's representative in the meeting room.
- 4. The group is responsible for letting their members in and holding the meeting. The door should never be propped open while the meeting is in progress.
- 5. The group is also responsible for making sure the outside door is latched when they leave. So long as the latch engages, the door is always locked.

Q: Would there still be a fee for reserving the room?

¹ Armstrong, Michael. "Homer Public Library Design Ahead of Schedule." *Homer News* 8 Jul. 2004. Web. 4 Jun. 2025. Page 13. https://homerpubliclibrary.newspapers.com.

A: The library currently charges \$50 per hour to use the room outside of regular service hours, which is largely cancelled out by the staff overtime needed to keep the whole building operational. Whether that fee should remain in place is open for debate—the City could decide to abolish it, which increases the use of the room, or keep it to generate revenue.

Q: Would there be a damage deposit?

A: Another question for debate. We don't currently require a damage deposit. We could start with one and adjust it over time, or even require groups to demonstrate proof of insurance.

Any such requirements would reduce the usability of the room.

Q: How do other libraries manage their meeting rooms after hours?

A: Policies vary widely, but here's a sampling.

- Palmer Public Library (former building): Essentially the same process we propose.
 Staff locked the internal and external doors at closing time, and groups had to arrive before then to have access to the meeting room. Groups were responsible for making sure the restrooms were empty, lights were off and exterior doors latched before leaving. They never had a problem with vandalism or negligence.
- Big Lake Public Library: Groups must be present at closing time and staff lock the
 security grille, much as we propose here. Unlike in Homer, the group's representative
 gets a building key, which they deposit in the book drop after the meeting. The
 meeting room/restrooms are used outside of regular hours a couple of times a month.
 Use is free as long as the meeting begins by closing time; if staff have to come in to
 provide access outside of regular hours, there is a \$40/hour charge.
- Unalaska Public Library: Staff love having the security grille. The meeting
 room/lobby/restrooms are used constantly, particularly in the morning before 10 am
 opening. They've never had a problem with vandalism, but it's essential to make sure
 that a group's representative is listed on the reservation form and is present for the
 entire meeting.
- Soldotna Public Library: The grille closes off the meeting room, lobby and restrooms from the rest of the building. There is a \$30 charge for after-hours use, or \$60 for events charging an admission fee.

- Ketchikan Public Library: The grille can separate the meeting room/lobby/restrooms
 from the library, but policy says that staff must still stay behind to lock the outside
 doors after the meeting.
- Wasilla Public Library: The meeting room can be used outside of regular hours only if a staff member attends the meeting.
- Nome Public Library: There are several rooms with outside doors, with internal locks
 to prevent access to the rest of the building; restrooms are not available. Groups must
 fill out a reservation form. Staff must either stay in the building or else return after the
 meeting to lock up.
- Kodiak Public Library: The city council meets in the room weekly, and staff close the security grille if the meeting goes past closing time. No other meetings are allowed outside of regular hours.
- Juneau Public Library (Valley and Douglas branches): The meeting rooms are available before and after regular hours, and are used as polling places. The library charges a fee for meetings outside open hours.
- Seward Community Library and Museum: Groups reserve the room ahead of time.
 During normal hours they check out a pouch containing a building key and an alarm fob, which they return in the book drop. There is no charge for the room unless the event is for-profit. There have never been major problems in recent memory, but the library retains the right to charge a \$100 cleaning fee if necessary.
- Bethel Public Library: The library is inside the cultural center, which manages the
 meeting rooms. There is a fee for using the rooms, and some groups are allowed to
 check out the building key and meet when staff aren't present.

Q: Does the proposed grille obstruct the walkway?

A: No. The grille folds away into a pocket-wall on the north side of the corridor. That wall extends 30 inches into the hallway, almost exactly the same distance as the wooden shelving unit already there. The path into the building is the same straight line that exists now.

Q: Does it obstruct the view?

A: The grille requires a pocket wall on one side of the hallway and an overhead rail to slide on. There is some visual impact, but the equipment is hidden behind drywall, which can be painted or wood-paneled to blend in with the rest of the building. See the mockup photos for a rough idea of the possibilities.

Q: What about emergencies?

A: The grille will always be open except when an evening meeting is in progress. Even when the grille is closed, people can escape from inside the building through an emergency exit built right into the grille itself, with no key needed. On May 29, 2025, the State Fire Marshal issued a certificate approving the design as meeting all fire-code requirements.

Q: How much should this cost?

| | Funded | Costs |
|---|----------|----------|
| Original Council appropriation through Ord. 24-24(A) | \$30,000 | |
| Costs paid to June 12, 2025 | | |
| Architectural and engineering design | | \$11,241 |
| Fire Marshal plan review | | \$422 |
| Subtotal | | \$11,663 |
| Remaining costs (estimate as of February 25 | , 2025) | |
| Materials (including the grille itself, the support structures, and | | \$31,692 |
| various repairs to finishings after installation) | | 331,032 |
| Labor for installation | | \$2,727 |
| Contingencies | | \$1,721 |
| Estimated 4% annual inflation to May 2025 | | \$361 |
| Subtotal | | \$36,501 |
| Grand totals | | |
| Remaining unspent funds | \$18,337 | |
| Unfunded costs | | \$18,164 |
| Complete project costs | | \$48,164 |

Q: These cost estimates seem high. Can't this be done cheaper?

A: Probably not. People tend to assume that installing a grille is as simple as throwing a homemade concertina door across the space. I wish it was that easy! Here are some of the design challenges that have already been confronted:

- As a public building, the library has to meet fairly stringent fire code regulations. The
 grille closes off the building's main exit, which means it must incorporate an
 emergency exit door that can be opened from the inside without a key. The proposed
 design is a commercial product which includes such a door.
- 2. The floor is a concrete slab with underfloor heating pipes, which means you have to be very careful where you drill to put in supports.
- 3. There are also pipes crossing through the space just below the ceiling. The grille must be suspended from the overhead I-beam in such a way that it doesn't cut through the pipes.
- 4. The current design reaches the full height of the corridor. It might be possible to reduce costs by installing a grille that is only half-height, but it means putting in a heavy overhead beam about eight feet above floor level and spanning the entire width of the hallway. We felt this is an unsightly visual obstruction in a beautiful building and also blocks the view from some of the security cameras.

Q: Could a local manufacturer make a grille?

A: Maybe. We haven't put the construction and installation out to bid yet. The current design uses an off-the-shelf product. If we ask a local company to fabricate a custom job, the design work will have to be done again. Alternatively, if a local company was willing to work from the existing design but offer lower labor costs, that could change the numbers significantly.

Q: How much disruption would there be to library operations while the grille was under construction?

A: That has to be worked out with the contractor doing the installation, and minimizing the disruption would be a factor in evaluating the responses to the Request for Proposals, whenever that's issued.

Ideally, the construction work could be done outside of library hours, which would allow the entrance to be used normally. Failing that, we could route traffic through other doors, which have their own problems: the two emergency exists are not designed for wheelchairs, and sending people through the back entrance means passing through the staff work areas. If the construction could be done quickly, closing the building for a few days might be an option.

Q: Is there grant funding for projects like this?

A: We hope so! We're exploring grant options now. We have the final engineering drawings and approval from the Fire Marshal, so we're in a strong position for writing applications.





HOMER LIBRARY SECURITY GRILL

PERMIT SET

FOR:

CITY OF HOMER HOMER, ALASKA



PREPARED BY:



Anchorage, AK

2700 Gambell St, Ste 500 Anchorage, AK 99503 Phone: 907.743.3200 www.respec.com AECC163270

SHEET INDEX

NAME NUMBER **COVER SHEET**

LIFE SAFETY PLAN

SECURITY GRILL PLAN AND ELEVATIONS

GENERAL NOTES

STRUCTURAL DETAILS


10306.24019


PROJECT: HOMER PUBLIC LIBRARY - SECURITY GRILL ADDITION 500 HAZEL AVE. HOMER, AK CLIENT: CITY OF HOMER CONTRACTOR TBD SCOPE OF WORK: INSTALL A NEW SIDE ROLLING SECURITY GRILL BETWEEN THE PUBLIC LOBBY, CONFERENCE AND PUBLIC RESTROOMS OPEN FOR PUBLIC USE DURING LIBRARY OFF HOURS. ORIGINAL CODES - 2000 INTERNATIONAL FAMILY OF CODES CURRENT CODES - 2021 INTERNATIONAL FAMILY OF CODES WHERE APPLICABLE. INCLUDING: -2021 EXISTING BUILDING CODE LEVEL 2 ALTERATION (SECTION 603) CONSTRUCTION TYPE: VB - FULLY AUTOMATIC SPRINKLERED OCCUPANCY TYPE: MIXED USE A-3/PUBLIC LIBRARY, B/OFFICE, S-1/STORAGE FULLY SPRINKLERED AND ALARMED (SUPERVISED) LEVEL 2 ALTERATION (IEBC 603) 5/8/25 EXISTING OCCUPANT LOAD CALCULATION: PER 2000 IBC, TABLE 1003.2.2.2 OCCUPANT LOAD IS CALCULATED AT 50 NET FOR READING ROOMS, 100 GROSS FOR STACK AREAS, 100 GROSS FOR OFFICE AREAS, 300 GROSS ACCESSORY STORAGE/MECHANICAL ROOMS, 15 NET FOR ASSEMBLY AREAS (LOBBY, MEETING W/ UNCONCENTRATED TABLES AND CHAIRS = TOTAL OF 220 TOTAL OCCUPANTS EGRESS: CONFERENCE ROOM 280 SF/15 = 19 OCC. 1 EXIT REQUIRED/1 PROVIDED VESTIBULE/LOBBY 370 SF/15 = 25 OCC. 1 EXIT REQUIRED/ 1 PROVIDED TOTAL OCCUPANTS = 44 OCC. 1 EXIT REQUIRED/ 1 PROVIDED **CODE LEGEND** FIRE EXIT ● ● ● ■ SMOKE BARRIER FIRE EXTINQUISHER **ECURITY** (LOCATED IN ADJACENT WALL) CHECKED LIFE SAFETY PLAN PROJECT No. 10306.24019 SCALE: 1" = 20'-0" REVISIONS

Trent Mullins


No. Crust., Enterer multins disrepair. CONTINER Mullins

No. Crust., Enterer multins disrepai









3 SIDE FOLDING GRILL SECTION

A-101 SCALE: 1/4" = 1'-0"

GENERAL NOTES

- A. GENERAL CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS AND DIMENSIONS AT THE JOB SITE. REPORT DISCREPANCIES TO THE OWNER'S REPRESENTATIVE.
- B. WHERE DEMOLITION IS REQUIRED FOR NEW CONSTRUCTION REPAIR AREAS IN-KIND WITH MATCHING MATERIALS AND FINISHES (TYPICAL).
- C. CONTRACTOR TO VERIFY LOCATION OF EXISTING RADIANT IN-FLOOR SLAB TUBING TO AVOID CONFLICT WITH IN-FLOOR SECURITY GRILL ASSEMBLIES, REFER TO FLOOR SOCKET DETAIL 2/A-101 AND 4/S-101
- D. SECURITY GRILL BASIS OF DESIGN:
 - CORNELLCOOKSON VISTAPANE (MODEL ESC-31) SLOTTED ANODIZED ALUMINUM SIDE FOLDING SECURITY GRILL

 FIXER AT FOLDING FAIR AND LLOCK BOLT LOCKING ON
 - FIXED AT FOLDING END AND HOOK BOLT LOCKING ON SECURED CLOSURE SIDE
 - 3'-0"x7'-0" EMERGENCY EGRESS FALL AWAY DOOR
- E. PROVIDE COMPLETE SHOP DRAWINGS OF NEW SECURITY GRILL AND STACKING POCKET FOR REVIEW AND APPROVAL PRIOR TO COMMENCING WORK. COORDINATE ALL WORK WITH EXISTING AND NEW ASSEMBLIES IN ORDER TO ACCOMPLISH THE SCOPE OF WORK HEREIN.

Trent Mullins Constitution of the Mullins No. AELA11194

5/88/25

No. AELA11194

5/88/25



R LIBRARY SECURITY GRILI

SHEET TITLE :
SECURITY GRILL PLAN AND
ELEVATIONS


ELEVATIONS

DESIGN
DRAWN
CHECKED
DATE 02/28/
PROJECT No.
10306.24019

A-101

KEY PLAN

REVISIONS



STRUCTURAL GENERAL NOTES

- 1. PERFORM ALL WORK IN COMPLIANCE WITH THE MINIMUM STANDARDS OF THE FOLLOWING CODES:
- A. THE INTERNATIONAL BUILDING CODE (IBC) 2021 AND ITS REFERENCED STANDARDS, HEREIN REFERRED TO AS "THE CODE", THE UNIFIED FACILITIES CRITERIA (UFC), SECTIONS 03-04 AND OTHER REGULATORY CRITERIA WHICH HAVE AUTHORITY OVER ANY PORTION OF THE WORK.
- 2. THIS WORK INVOLVES EXISTING STRUCTURES, PERFORM THE FOLLOWING TASKS PRIOR TO STARTING CONSTRUCTION:
 - A. SURVEY AND FIELD VERIFY ALL EXISTING CONDITIONS ASSOCIATED WITH THE WORK.
 - B. ALL OMISSIONS OR CONFLICTS BETWEEN ELEMENTS OF THE CONTRACT DOCUMENTS MUST BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ENGINEER OF RECORD, PRIOR TO PROCEEDING WITH THE RELATED WORK.
- 3. THE STRUCTURAL DRAWINGS REPRESENT THE FINISHED STRUCTURE AND DO NOT INDICATE THE METHOD OF CONSTRUCTION. CONSTRUCTION LOADS MUST NOT EXCEED THE DESIGN LIVE LOADS.
- I. IF THE STRUCTURAL ENGINEER OF RECORD IS NOT RETAINED BY THE OWNER TO OVERSEE CONSTRUCTION ACTIVITIES, THE STRUCTURAL ENGINEER OF RECORD IS NOT IN RESPONSIBLE CHARGE OF THE CONSTRUCTION PER SECTION 107.3.4 OF THE CODE. CONSTRUCTION ACTIVITIES INCLUDE, BUT ARE NOT LIMITED TO, REVIEW OF SPECIAL INSPECTION AND STRUCTURAL OBSERVATION REPORTS, REVIEW OF SUBMITTAL DOCUMENTS, AND REVIEW DELEGATED DESIGN SUBMITTALS.

STRUCTURAL DESIGN DATA

- 1. RISK CATEGORY
- 2. SECURITY GRILL:
 - A. CORNELL VISTAPANE 36 PLF OR 370 LBS CONCENTRATED
- 3. SEISMIC LOADS:

| A. | SEISMIC IMPORTANCE FACTOR | $I_e = 1.0$ |
|----|--------------------------------|-----------------------|
| B. | SITE CLASS | D - DEFAULT |
| C. | MAPPED ACCELERATIONS | |
| | a. SHORT-PERIOD | S _S = 1.5 |
| | b. 1-SECOND | $S_1 = 0.603$ |
| D. | DESIGN ACCELERATIONS | |
| | a. SHORT-PERIOD | S _{DS} = 1.2 |
| E. | COMPONENT AMPLIFICATION FACTOR | a = 1.0 |
| | | |

R = 2.5

 $E_h = 231 LBS$ $E_v = 102 LBS$

F. RESPONSE MODIFICATION FACTOR

G. DESIGN BASE SHEAR

STRUCTURAL STEEL NOTES

- 1. DETAIL, FABRICATE, AND ERECT ALL WORK IN CONFORMANCE WITH CHAPTER 22 OF THE IBC AND ALL REFERENCED STANDARDS.
- 2. USE STRUCTURAL STEEL CONFORMING TO THE FOLLOWING STANDARDS, UNLESS NOTED OTHERWISE:

| SHAPE | YIELD STRENGTH | MATERIAL NOTES |
|--------------------------------|----------------|----------------|
| C, L, PLATES, MISCELLANEOUS | 36 KSI | ASTM A36 |

- 3. BOLT AND ANCHOR ROD REQUIREMENTS:
 - A. USE BOLTS, NUTS AND WASHERS CONFORMING TO THE REQUIREMENTS OF ASTM F3125 GRADE A325 OR A490.
- 4. BOLTED CONNECTION REQUIREMENTS:
 - A. USE SIMPLE SHEAR CONNECTIONS WITH A MINIMUM OF TWO HIGH-STRENGTH BOLTS IN BEARING TYPE CONNECTIONS, THREADS MAY BE INCLUDED OR EXCLUDED FROM SHEAR PLANE(S), UNLESS NOTED OTHERWISE.
 - B. TIGHTEN ALL BOLTS TO A SNUG-TIGHT CONDITION, SUCH THAT ALL PLIES ARE IN SNUG CONTACT, UNLESS NOTED OTHERWISE
- 5. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR THE CONTROL OF ALL ERECTION PROCEDURES AND SEQUENCE.
- 6. DO NOT FIELD CUT OR MODIFY STRUCTURAL STEEL MEMBERS FOR THE WORK OF OTHER TRADES WITHOUT PRIOR WRITTEN APPROVAL OF THE ENGINEER OF RECORD.

STRUCTURAL COLD FORMED METAL NOTES

- 1. ALL COLD FORMED STEEL SHAPES MUST MEET OR EXCEED THE FOLLOWING REQUIREMENTS:
- A. 54 MILS (16 GA) AND THICKER ASTM A446 GRADE D ($F_Y = 50 \text{ KSI}$)
- B. 43 MILS (18 GA) AND THINNER ASTM A446 GRADE A ($F_Y = 33$ KSI)
- 2. THE CONTRACTOR MUST PROVIDE ALL ACCESSORIES, NOT SPECIFICALLY DETAILED IN THESE DRAWINGS, IN CONFORMANCE WITH THE MANUFACTURERS RECOMMENDATION.
- 3. ALL SELF-DRILLING SHEET METAL SCREWS MUST PROTRUDE 1/4" THROUGH THE METAL STUD FRAMING. SCREWS MUST BE INSTALLED AND TIGHTENED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.

STRUCTURAL WOOD NOTES

- 1. PERFORM ALL WORK STRUCTURAL WOOD WORK IN CONFORMANCE WITH CHAPTER 23 OF THE IBC, AND ALL REFERENCED STANDARDS.
- 2. USE CONVENTIONAL FRAMING MATERIALS MEETING OR EXCEEDING THE FOLLOWING MINIMUM REQUIREMENTS:

| USE | DIMENSIONS | SPECIES | GRADE | Fb (PSI) |
|--------|------------|----------|-------|----------|
| HEADER | 4x10 | DOUG-FIR | No. 2 | 900 |

- A. USE VISUALLY GRADED OR MACHINE STRESS RATED LUMBER IN ACCORDANCE WITH THE LATEST EDITIONS OF THE WEST COAST LUMBER INSPECTION BUREAU (WCLIB) TECHNICAL PUBLICATION NO. 17 OR THE WESTERN WOOD PRODUCTS ASSOCIATION (WWPA) "WESTERN LUMBER GRADING RULES (G5)".
- 3. USE CONNECTION HARDWARE MEETING THE FOLLOWING REQUIREMENTS, UNLESS NOTED OTHERWISE ON PLANS:
 - A. USE BOLTS CONFORMING TO ASTM A307 WITH STANDARD WASHERS UNDER ALL BOLT HEADS AND NUTS CONTACTING WOOD.
 - B. USE COMMON WIRE NAILS OF SIZES NOTED ON DRAWINGS. IF ALTERNATIVE FASTENERS ARE DESIRED, THE CONTRACTOR IS RESPONSIBLE FOR SUBMITTING A SCHEDULE OF SUBSTITUTIONS, SHOWING EQUIVALENT FASTENER STRENGTHS.
- 4. DO NOT FIELD CUT STRUCTURAL WOOD MEMBERS FOR THE WORK OF OTHER TRADES WITHOUT THE PRIOR REVIEW OF THE ENGINEER.
- 5. DO NOT USE WOOD TREATMENTS OR PRESERVATIVES WITHOUT SUBMITTAL AND REVIEW BY THE ENGINEER OF RECORD.

CONSULTANT:





LIBRARY SECURITY GRIL

HOM

AL NOTES

GENERAL

 CHECKED
 JEH

 DATE
 02/28/2025


 PROJECT No.

 10306.24019

DESIGN DRAWN


S-00

No. | Date | Item



INTERMEDIATE FLOOR SOCKET DETAIL

SCALE: 1 1/2" = 1'-0"



GRILI SECURITY DRAWN CHECKED PROJECT No. 10306.24019

02/28/2025

No. Date Item

Plan Review Approval Letter & Certificate
Grantor: State of Alaska, Department of Public Safety, Division of Fire & Life Safety
Grantee: HOMER CITY OF

Recording District: Legal Description:

| | State of Alaska |
|--|--|
| Offi | ice of the State Fire Marshal |
| | Plan Review |
| This is to certify that the pon5/29/2025 | plans for this building were reviewed by the State Fire Marshall for conformance with AS 18.70.010 100; 13 AAC 50.027. |
| This certificate shall be Homer Public Library (Ne | e posted in a conspicuous place on the premises named and shall remain |
| posted until construction | is completed. |
| NOTICE: Any changes review by the State Fire N | s or modifications to the approved plans must be resubmitted for Marshal. |
| Plan Review #: 2025 | 5ANCH0261 By: |
| Authority: AS 18.70.080 Form: 12-741 (6/01) Renovation | Jarrett Zuspan Building Plans Examiner I |



Department of Public Safety

DIVISION OF FIRE AND LIFE SAFETY

Plan Review Bureau – Anchorage 5700 East Tudor Road Anchorage, Alaska 99705-1225 Main: 907.269.2004 Fax:907.269.0098

06/04/2025

Return to Applicant: Leon Galbraith

3575 Heath St. Homer, AK 99603

SUBJECT: Homer Public Library (New Location Hazel Ave) - Renovation

ADDRESS: 500 Hazel Avenue

CITY: Homer

PLAN REVIEW: 2025ANCH0261

TYPE OF CONTRUCTION: V-B
OCCUPANCY: B Business

ADDITIONAL OCCUPANCY: A-3 Assembly, churches, community halls, gyms

2021 INTERNATIONAL BUILDING AND FIRE CODE

Dear Leon Galbraith:

Plans for the Renovation have been reviewed by this office for conformity with the State Fire Safety Regulations and are hereby approved. Enclosed is a certificate of approval that must be posted on the premises until completion of the above project.

It is prohibited to occupy this building until construction is completed, and if applicable, the Automatic Fire System(s) is installed, tested, and certified as operable. Any changes to the approved plans must be submitted to this office for review and approval.

Approval of submitted plans is not approval of omissions or oversights by this office or noncompliance with any applicable regulations of the Municipal Government. The plans have not been reviewed for compliance with the federal Americans with Disabilities Act or structural requirements.

It must be understood that the inclusion of and compliance with State Fire Safety Regulations does not preclude the necessity of compliance with the requirements of local codes and ordinances.

If we can be of further assistance in this matter, please feel free to contact us at the address above.

Approved By: Jarrett Zuspan Building Plans Examiner I jarrett.zuspan@alaska.gov

Enclosure: Approval Certificate

Side-Folding Grille Gates

Side-folding grilles provide a convenient and smooth operation for many businesses. These interior sliding security gates move to each side to open rather than raise and lower. They provide excellent protection while maintaining high visibility and ventilation.

The Cornell lineup of side-folding doors includes:

- VistaPane™: VistaPane sports a unique design with solid, perforated, slotted, or transparent panels. Choose from panel materials like aluminum, tempered glass, steel, or Lexan. Vistapane offers pocket-door style retraction as an option.
- VisionGlide[™]: The lightweight VisionGlide is ideal for curved tracks and spaces with less structural support. Select from an attractive aluminum finish with a straight or brick pattern design.
- GlideGard™: This side-folding grille offers high security with many customization options to increase visual appeal. Add clear anodized rods or other style
 features to boost its look.

VISTAPANE™ SIDE FOLDING GRILLES

Side Folding Grilles

Model Number: ESC31

Side Folding Security Grilles

VistaPane[™] Side Folding Closures can provide a range of benefits – from the visibility and airflow of an open-design grille to the maximum security offered by a solid pane. We offer five different panel options to meet your varied needs.

Features:

- Clear anodized truss panels and posts
- Custom wet paint available, consult factory
- Hook bolt locking with cylinders both sides standard, other locking optional
- Emergency egress option Bi-part or full 3' x 7' egress door within the curtain
- 14" radius 90°, 120°, 135° and 150° curves standard

VistaPane™ Side-Folding Security Grilles

VistaPane™ side-folding security grilles deliver a high level of security while maintaining excellent visibility and airflow. These folding security grilles feature a paneled design with multiple styles available to match your preferences, including solid, slotted, perforated, and transparent panels made from aluminum, steel, tempered glass, or shatter-resistant Lexan. VistaPane™ side-folding security grilles come with several customization options, including a heavy-duty steel pocket door for concealment when stored.

Sizes

| Curtain Type | Maximum Height | Lbs. Per Sq. Ft. |
|----------------------|----------------|------------------|
| Perforated VistaPane | 14' 0" | 2.0 |
| Slotted VistaPane | 20' 0" | 2.2 |
| Lexan VistaPane | 14' 0" | 2.25 |
| Glass VistaPane | 12' 0" | 2.5 |
| Solid VistaPane | 20' 0" | 2.25 |

Slotted Panels

This design features aluminum panels with slots that provide a high level security with visual access and air flow. Interlocking components prevent forced entry. Aluminum panels are lighter than glass inserts, which require less bulkhead support and make it easier to operate. This panel type is excellent for storefront applications.

Slotted VistaPane™

- · 13 gauge fully anodized slotted aluminum panels
- 1 1/4" x 1/4" oblong slots
- · Extruded insert fits into framing hinge extrusion for superior security
- Maximum height: 20' 0"
- · Airflow through closure: 20%
- · Airflow through panel: 30%

Grille Single Slide or Bi Parting Construction

This side folding grille can be designed to close at the center of the room in divided sections or extend fully from one wall to the other.

Pocket Door

Available for side closing products up to 12 feet high, this heavy duty 12 gauge steel pocket door and frame assembly neatly closes off the pocket area of a stored partition.


Side Folding Closure: VistaPane™ Model ESC-31

VistaPane Standard Features:

- Clear Anodized Truss Panels and Posts
- Color Anodizing, Custom Paint consult factory
- Hook bolt locking with cylinders both sides standard, other locking optional



Optional Emergency Egress Door Shown



door within the curtain

ESC-31 VistaPane Slotted Aluminum

Slotted and Perforated Panels:

Emergency Egress Option- Bi-part or full 3' x 7' egress

14" radius 90 and 135° curves standard, others optional

See back for additional Design Construction Details.


Perforated with a pattern of slots that provides high level security with visual access and air flow. Interlocking components prevent forced entry. Lighter than glass inserts; requiring less bulkhead support and easy to operate. Excellent for storefront applications.

- VistaPane[™] Slotted
 - 13 Gauge Fully Anodized Slotted Aluminum Panels
 - 1 1/4" x 1/4" oblong slots
 - Extruded insert fits into framing hinge extrusion for superior security
 - Maximum Height: 20' 0"
 - Airflow Through Closure: 20%
 Airflow Through Panel: 30%
- VistaPane[™] Perforated
 - 3/16" Perforated 18 Gauge Steel Panels
 - Maximum Height: 14' 0"
 - Airflow Through Closure: 39% Airflow Through Panel: 47%



ESC-31 VistaPane Perforated Steel





ESC-31 VistaPane[™] Glass or Lexan

Glass and Lexan Panels:

Clear, shatterproof Lexan® or tempered glass inserts allow unobstructed views while providing solid security and blocking refuse, odor and smoke.


- VistaPane[™] Lexan
 - 1/8" Thick Lexan Panels
 - Maximum Height: 14' 0"
- VistaPane[™] Glass
 - Clear Tempered Glass Panels
 - Maximum Height: 12' 0"

Solid Panels:

Full height aluminum panels and heavy gauge dedicated extrusions deny visual access and provide solid security.


- VistaPane[™] Solid
 - 13 Gauge Clear Anodized Solid Aluminum Panels
 - · Maximum Height: 20' 0"






ESC-31 VistaPane[™] Solid

Side Folding Grille Details



Vertical Upright Members



Top & Bottom Bottom Locking Intermediate: Locking End Cylinder Control

or Intermediate Located at the beginning of a curtain or curtain section, these members contain a top and bottom drop bolt lock for engagement at the floor and ceiling.

Spring Knob Located throughout the curtain so that any open section does not exceed 13'. These members have a drop bolt lock for engage-

ment at the floor.

Bi-Part

Located at all curtain bi-part sections, these members have an attached strike channel for matching up with a lead member and a drop bolt lock for engagement at the floor.

Floating End With an attached full height protection plate and located within these members

a stack pocket. float from the back to a set minimum projection in the pocket being stopped by track and floor mounted stoppers.

Hookbolt and Wall Striker

These members exposed join a wall or member mounted strike channel and contain a hook bolt lock that engages the strike channel. direct

Fixed End Normally used

on grilles with stacking, these members are set up with a full height wall mounting plate or angle for attachment to the wall.

Design Construction

- Minimal headroom required A 1 3/4' high by 1 5/16" wide track mounts to overhead structure to support the unit.
- No floor track is required.
- Maximum recommended width of a single unit section is 30' 0" (before using a bi-parting unit).
- Maximum intermediate member spacing is 13' for full height units, 7' for countertop units.
- Operation is manual push / pull only.
- Minimum height for all units is 2'0". minimum width for all units is 4'0".
- Maximum height: see below.
- The grille support should be designed to carry the weight of a fully stacked door at any point along its length. See below.

| | Maximum Height | Lbs. Per Sq. Ft. |
|----------------------|-------------------|---------------------|
| VisionGlide | 12' 0" | 0.8 |
| GlideGard | 14' 0" | 1.5 |
| VistaPane Perforated | 14' 0" | 2.0 |
| VistaPane Slotted | 20' 0" | 2.2 |
| VistaPane Lexan | 14' 0" | 2.25 |
| VistaPane Glass | 12' 0" | 2.5 |
| VistaPane Solid | 20' 0" | 2.25 |

Special Feature Options

■ Pocket Door - Available option for side folding grilles to neatly finish off pocket openings. Both the pocket door and frame are made of heavy duty 12 gauge steel that is coated with a baked-on polyester powder coat finish. Available up to 12' in height and fit pocket openings from 10" to 24" wide.



Multiple Height Units -Available for openings that have a full height and a countertop area. This is accommodated

with a bi-part unit or with a single pocket unit when the pocket is located at the full height side of the opening.

Optional Finishes

For standard clear anodized components:


- Color Anodized: medium bronze. dark bronze or champagne
- Custom Wet Paint: consult factory



An ISO 9001:2008 Registered Company

Crestwood Industrial Park • Mountaintop, PA 18707 • TEL 800.233.8366 • FAX 800.526.0841 Architect & Design Support Dept.: Ext. 4551 • Email: ADS@cornelliron.com

Website: www.cornelliron.com



100% DESIGN SUBMITTAL CONSTRUCTION COST ESTIMATE

HOMER LIBRARY SECURITY GRILLE HOMER, ALASKA

PREPARED FOR:

RESPEC 2700 Gambell Street, Suite 500 Anchorage, Alaska 99503

February 25, 2025



DATE: 2/25/2025

HMS Project No.: 24135

NOTES REGARDING THE PREPARATION OF THIS ESTIMATE

DRAWINGS AND DOCUMENTS

Level of Documents: (5) 100% design documents

Date: February 7, 2025

Provided By: RESPEC of Anchorage, Alaska

RATES

Pricing is based on current material, equipment and freight costs.

Labor Rates: A.S. Title 36 working 60 hours per week

Premium Time: 16.70% Subcontractor's Mark-Up: 35.00%

BIDDING ASSUMPTIONS

Contract: Standard construction contract without restrictive bidding clauses

Bidding Situation: Competitive bids assumed

Bid Date: May 2025 Start of Construction: Summer 2025

EXCLUDED COSTS

- 1. A/E design fees
- 2. Administrative and management costs
- 3. Furniture, furnishings and equipment (except those specifically included)
- 4. Remediation of contaminated soils or abatement of any hazardous materials, if found during construction
- 5. Sales tax, unless otherwise noted

DATE: 2/25/2025

HMS Project No.: 24135

NOTES REGARDING THE PREPARATION OF THIS ESTIMATE (Continued)

GENERAL

When included in HMS Inc.'s scope of services, opinions or estimates of probable construction costs are prepared on the basis of HMS Inc.'s experience and qualifications and represent HMS Inc.'s judgment as a professional generally familiar with the industry. However, since HMS Inc. has no control over the cost of labor, materials, equipment or services furnished by others, over contractor's methods of determining prices, or over competitive bidding or market conditions, HMS Inc. cannot and does not guarantee that proposals, bids, or actual construction cost will not vary from HMS Inc.'s opinions or estimates of probable construction cost.

This estimate assumes continued normal escalation based on the current economic climate. HMS Inc. will continue to monitor this, as well as other international, domestic and local events, and the resulting construction climate, and will adjust costs and contingencies as deemed appropriate.

HOMER LIBRARY SECURITY GRILLE HOMER, ALASKA 100% DESIGN SUBMITTAL CONSTRUCTION COST ESTIMATE PAGE 4

DATE: 2/25/2025

HMS Project No.: 24135

GENERAL COST SUMMARY

| | Total |
|----------|-----------|
| BASE BID | \$ 36,501 |
| OPTION 1 | 881 |
| | |

DATE: 2/25/2025

HMS Project No.: 24135

100% DESIGN COST SUMMARY

| | | Material | Labor | Total | |
|------------------------------|-------|-----------|----------|-----------------|--|
| | | | | | |
| 01 - SITE WORK | | \$ 356 | \$ 752 | \$ 1,108 | |
| 02 - SUBSTRUCTURE | | 0 | 0 | 0 | |
| 03 - SUPERSTRUCTURE | | 0 | 0 | 0 | |
| 04 - EXTERIOR CLOSURE | | 0 | 0 | 0 | |
| 05 - ROOF SYSTEMS | | 0 | 0 | 0 | |
| 06 - INTERIOR CONSTRUCTION | | 31,336 | 1,975 | 33,311 | |
| 07 - CONVEYING SYSTEMS | | 0 | 0 | 0 | |
| 08 - MECHANICAL | | 0 | 0 | 0 | |
| 09 - ELECTRICAL | | 0 | 0 | 0 | |
| 10 - EQUIPMENT | | 0 | 0 | 0 | |
| 11 - SPECIAL CONSTRUCTION | | 0 | 0 | 0 | |
| SUBTOTAL: | | \$ 31,692 | \$ 2,727 | \$ 34,419 | |
| 12 - GENERAL REQUIREMENTS | | | Included | d in Door Quote | |
| SUBTOTAL: | | | | \$ 34,419 | |
| 13 - CONTINGENCIES | | | | | |
| Design Unknowns | 5.00% | | | 1,721 | |
| Escalation to May 2025 at | | | | | |
| 4% per Annum (3 Months) | 1.00% | | | 361 | |
| TOTAL ESTIMATED CONSTRUCTION | COST: | | | \$ 36,501 | |

DATE: 2/25/2025

HMS Project No.: 24135

ELEMENTAL SUMMARY

| | | | Total | |
|----------------------------------|-----------|--------|----------------|------------|
| Element | Material | Labor | Material/Labor | Total Cost |
| 01 - SITE WORK | | | | \$ 1,108 |
| 011 - Hazmat Abatement | \$ 0 | \$ 0 | \$ 0 | |
| 012 - Site Preparation | 356 | 752 | 1,108 | |
| 013 - Site Improvements | 0 | 0 | 0 | |
| 014 - Site Mechanical | 0 | 0 | 0 | |
| 015 - Site Electrical | 0 | 0 | 0 | |
| 02 - SUBSTRUCTURE | | | | \$ O |
| 021 - Standard Foundations | \$ 0 | \$ 0 | \$ 0 | |
| 022 - Slab on Grade | 0 | 0 | 0 | |
| 023 - Basement | 0 | 0 | 0 | |
| 024 - Special Foundations | 0 | 0 | 0 | |
| 03 - SUPERSTRUCTURE | | | | \$ O |
| 031 - Floor Construction | \$ 0 | \$ 0 | \$ 0 | |
| 032 - Roof Construction | 0 | 0 | 0 | |
| 033 - Stair Construction | 0 | 0 | 0 | |
| 04 - EXTERIOR CLOSURE | | | | \$ O |
| 041 - Exterior Walls | \$ 0 | \$ 0 | \$ 0 | · |
| 042 - Exterior Doors and Windows | 0 | 0 | 0 | |
| 05 - ROOF SYSTEMS | | | | \$ 0 |
| 051 - Roofing | \$ 0 | \$ 0 | \$ 0 | 7 • |
| 052 - Skylights | 0 | 0 | 0 | |
| 06 - INTERIOR CONSTRUCTION | | | | \$ 33,311 |
| 061 - Partitions and Doors | \$ 30,961 | \$ 417 | \$ 31,378 | φ 33,0 i i |
| 062 - Interior Finishes | 375 | 1,558 | 1,933 | |
| 063 - Specialties | 0 | 0 | 0 | |
| 07 - CONVEYING SYSTEMS | \$ 0 | \$ 0 | | \$ 0 |

DATE: 2/25/2025

HMS Project No.: 24135

ELEMENTAL SUMMARY

| | | | Total | |
|-----------------------------------|-----------|----------|----------------|------------|
| Element | Material | Labor | Material/Labor | Total Cost |
| 08 - MECHANICAL | | | | \$ O |
| 081 - Demolition | \$ 0 | \$ 0 | \$ 0 | |
| 082 - Plumbing | 0 | 0 | 0 | |
| 083 - HVAC | 0 | 0 | 0 | |
| 084 - Fire Protection | 0 | 0 | 0 | |
| 085 - Special Mechanical Systems | 0 | 0 | 0 | |
| 09 - ELECTRICAL | | | | \$ O |
| 091 - Demolition | \$ 0 | \$ 0 | \$ 0 | |
| 092 - Service and Distribution | 0 | 0 | 0 | |
| 093 - Lighting and Power | 0 | 0 | 0 | |
| 094 - Special Electrical Systems | 0 | 0 | 0 | |
| 10 - EQUIPMENT | | | | \$ 0 |
| 101 - Fixed and Movable Equipment | \$ 0 | \$ 0 | \$ 0 | |
| 102 - Furnishings | 0 | 0 | 0 | |
| 11 - SPECIAL CONSTRUCTION | \$ O | \$ 0 | | \$ 0 |
| SUBTOTAL DIRECT WORK: | \$ 31,692 | \$ 2,727 | | \$ 34,419 |
| | | | | |

DATE: 2/25/2025

HMS Project No.: 24135

| 01 - SITE WORK | QUANTITY | QUANTITY | QUANTITY | | | MATERIAL | | LABOR | | TOTAL | TOTAL |
|---------------------------|----------|----------|----------|--------|------------|-------------|------------|-------------|-----------------|----------------------|-------|
| 012 - Site Preparation | | | | UNIT | RATE \$ | TOTAL \$ | RATE \$ | TOTAL \$ | UNIT RATE \$ | MATERIAL/LABOR \$ | |
| <u>DEMOLITION</u> | | | | | | | L | | | | |
| Demolish wall finish | 32 | SF | 0.20 | 6 | 4.50 | 144 | 4.70 | 150 | | | |
| Protect existing finishes | 1,000 | SF | 0.35 | 350 | 0.50 | 500 | 0.85 | 850 | | | |
| SUBTOTAL: | | | _ | \$ 356 | | \$ 644 | | \$ 1,000 | | | |
| Labor Premium Time | 16.70% | | | | | 108 | | 108 | | | |

DATE: 2/25/2025

HMS Project No.: 24135

| 06 - INTERIOR CONSTRUCTION | | | MATERIAL | | LABOR | | TOTAL | TOTAL |
|--|----------|------|------------|-------------|------------|-------------|-----------------|----------------------|
| 061 - Partitions and Doors | QUANTITY | UNIT | RATE \$ | TOTAL \$ | RATE \$ | TOTAL \$ | UNIT RATE \$ | MATERIAL/LABOR \$ |
| 3 1/2" metal stud partitions | 75 | SF | 1.42 | 107 | 1.90 | 143 | 3.32 | 250 |
| 3"x10" header with associated hardware | 11 | LF | 7.00 | 77 | 8.00 | 88 | 15.00 | 165 |
| 1/2" all thread with stiffener | 6 | EA | 21.00 | 126 | 21.00 | 126 | 42.00 | 252 |
| 10'9"x15'10" horizontal side folding grille (quote per Hunter at Door Systems of Alaska, 907-931-9500) | 1 | EA | 30651.00 | 30,651 | | | 30651.00 | 30,651 |
| SUBTOTAL: | | | _ | \$ 30,961 | | \$ 357 | | \$ 31,318 |
| Labor Premium Time | 16.70% | | | | | 60 | | 60 |

| TOTAL ESTIMATED COST: \$ 30,961 \$ 417 \$ 31 | \$ 30,961 |
|--|-----------|
|--|-----------|

DATE: 2/25/2025

HMS Project No.: 24135

| 06 - INTERIOR CONSTRUCTION | | | MATERIAL | | LABOR | | TOTAL | TOTAL |
|----------------------------|----------|------|------------|-------------|------------|-------------|-----------------|----------------------|
| 062 - Interior Finishes | QUANTITY | UNIT | RATE \$ | TOTAL \$ | RATE \$ | TOTAL \$ | UNIT RATE \$ | MATERIAL/LABOR \$ |
| 5/8" Type X gypboard | 150 | SF | 1.10 | 165 | 1.70 | 255 | 2.80 | 420 |
| Paint gypboard (allowance) | 600 | SF | 0.35 | 210 | 1.80 | 1,080 | 2.15 | 1,290 |
| SUBTOTAL: | | | _ | \$ 375 | | \$ 1,335 | | \$ 1,710 |
| Labor Premium Time | 16.70% | | | | | 223 | | 223 |

DATE: 2/25/2025

HMS Project No.: 24135

| OPTION 1 | QUANTITY | UNIT | MATERIA RATE \$ | TOTAL \$ | LABC RATE \$ | OR TOTAL \$ | TOTAL UNIT RATE \$ | TOTAL MATERIAL/LABOR \$ |
|------------------------|----------|------|-----------------------|-------------|--------------------|-------------------|--------------------|-------------------------------|
| Anodized grille finish | 1 | EA | 881.00 | 881 | | | 881.00 | 881 |
| SUBTOTAL: | | | _ | \$ 881 | | | | \$ 881 |

Labor Premium Time 16.70%